

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N.R. 11W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 32 and 33.

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 7-7-63 with George Hamilton, Ass't.

WITNESSES TO CORNER..... 11" Red Pine (1/4 S. N.B.T.) N. 89° W., 64 lks.



14" Red Pine (1/4 S. N.B.T.) S. 44° W., 114 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate distance
between two Sec. Cors. and in a North-South Fire lane.

Found no evidence of Original Cor.

SURVEYOR'S SEAL

SIGNED Billy O. Buckler DATE 4/27/64
REGISTERED LAND SURVEYOR