

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~48-49~~ NR ~~10-11~~ W

----- Luce -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 1-6-31-36 -----
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----
WITNESSES TO CORNER 12" W. Pine ----- S 38° W ----- 152 links -----
"S 1 T48N R11W NBT" -----
24" W. Pine ----- N 88° W ----- 175 links -----
"S 36 T49N R11W NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from two hemlock B.T.s bearing S 49° W 40 links. Tree green, face in excellent condition. Hemlock bearing S 41° E 34 links. Tree broken off above scribe marks which are very plain.

NOTE: Gov't notes give these B.T.s in NW and NE quadrant.

Found 2" iron pipe in place.

Corner found with Ass't D. F. Kutchera.

Corner placed and witnessed Dec. 20, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 12/20/57
REGISTERED LAND SURVEYOR