

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>48 &</sup><sub>49</sub> NR 11 & 12 W

--- Luce --- COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 6-1-36-31 or Town-  
ship Corner

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 11" Hard Maple (S6 NBT) S 11° E 23 Links

14" Hard Maple (S36 NBT) N 73° W 44 Links

14" Soft Maple (S31 NBT) N 18° E 35 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Replaced Corner as set by Marcus Schaaf, Reg. Surveyor.

Found 2" Iron Pipe in place with Yellow Birch B.T. (Green bearing S 23° W  
28 Links. B.T. in good condition. Also found Hemlock B.T. (not recorded) Green  
bearing S 69° E 36½ Links.

Corner placed and witnessed with J. Kutchera, Assistant District Forester  
and L. Rubick, Aide, on June 17, 1958.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 12/3/58  
REGISTERED LAND SURVEYOR