

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Luce COUNTY


T 49N R 11W

DESCRIPTION OF CORNER South 1/16 Cor. bet. Secs 23-24

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7/16/71

WITNESSES TO CORNER..... 11" W. Pine (S 1/16 BT) N61°W 33.1'



9" W. Pine (S 1/16 BT) S10°W 33.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.
This corner placed midway and on line bet. $\frac{1}{4}$ Cor. to north and Sec. Cor. to south.
Corner lies in N-S firelane and in line with a firelane to east.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

12/17/71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68