

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 49N N.R. 11W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 28-29

CORNER MONUMENT 1" pipe with 4" aluminum cap, buried in N-S firelane

DATE MONUMENT PLACED AND WITNESSED 8-25-70

WITNESSES TO CORNER..... 17" W. Pine (±S NBT) S86°W 9.3'



17" W. Pine (±S NBT) S78°E 10.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced as set by Marcus Schaaf, R.L.S.
Found where the iron pipe, set by Schaaf was removed by traffic.
Found remains of a Y. Pine B.T., lying on ground, near corner. Also found remains
of an old picket line bearing east of corner.

Corner lies 33' south of an old logging R.R. grade, course NW and SE.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-31-70
REGISTERED LAND SURVEYOR