

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 11 W.

Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17, 18, 19 and 20.

DESCRIPTION OF CORNER MONUMENT 3/8" X 18" Iron (buried)

WITNESSES TO CORNER 10" W. Pine S 52 W 61 Links (S 19 NBT)

12" R. Pine N 41 E 90 Links (S 17 NBT)

8" R. Pine N 66 W 58 1/2 Links (S 18 NBT)

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced as set by Schaaf in intersection of firelanes N-S-E-W.
Found remains of W. Pine stump S 10 W, 16 Links.

Set 3/8" X 18" Iron (buried).

Shown by McTiver, District Forester.

Corner was placed and witnessed on 10 June 1958.

SURVEYORS SEAL

SIGNED Billy D. Buckler
Billy D. Buckler DATE 5-27-59
REGISTERED LAND SURVEYOR