

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Luce Co.

3 Corners

| FOR CORNERS OF--                            | LOCATED IN--  | CORNER CODE NUMBER |
|---|---|--------------------|
| 1. PUBLIC LAND SURVEY _____                 | T. <u>49</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>11</u> <sup>E.</sup> / <sub>W.</sub>   | G-1, H-1           |
| 2. PROPERTY CONTROLLING IN SECTION <u>3</u> | , T. <u>49</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>11</u> <sup>E.</sup> / <sub>W.</sub> | 1-Sec.3            |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____  | , T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>         | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____       |   |                    |
| 5. PRIVATE CLAIMS _____                     |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-4, 19 76, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section and  $\frac{1}{4}$  corner set by John Burt D.S. in 1841. Bearings were:

- G-1 Sec. Cor. 3-4, T49N R11W and Sec's. 33-34, T50N R11W. W. Birch 14", N25°E, 24 lks. and Fir 7", N60°W, 8 lks.
- H-1 Quarter corner on North side of Sec. 3. Fir 7", N40°E, 17 lks. & W. Birch 14", N72°W, 24 lks.
- 1-Sec.3 West 1/16 corner on North side of Sec. 3.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-1 Re-established corner on a mean bearing bet. Section line on east side sec. 3 and the West line of Sec. 4. Found no evidence of original corner. Distance south to swamp checks well.
- H-1 Restored corner midway and on line bet. two sec. cors. Found no evidence of original corner.
- 1-Sec.3 Corner placed midway bet. sec. cor. to West and quarter corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners. Bearings are:

- G-1 5" W. Pine, N32°W, 29.8' & 8" soft Maple, S58°W, 59.4' & 9" Soft Maple, S42°E, 56.1' Corner lies on North slope and 10 feet North of a trail road. Distance North to old river bed = 50 feet.
- H-1 6" Soft Maple, N68°E, 9.5' & 9" Soft Maple, S55°W, 16.9' & 12" W. Pine, S61°E, 51.2'.
- 1-Sec.3 8" Red Pine, S26°W, 18.0' & 17" W. Birch, S57°E, 16.4' & Corner lies 15' North of Trail Road and on South slope of ridge.

SIGNED BY \_\_\_\_\_ DATE 3-25-80

Billy D. Buckler  
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

