

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. 8., R. 11 W.	H-3, L-9, B-9
2. PROPERTY CONTROLLING IN SECTION	12, T. 49 N. 8., R. 11 W.	13
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-3 North 1/4 Cor. of Sec. 10. D.N.R. on 5-7-63. 16" R. Pine, N38°E, 64 lks. & 14" R. Pine, S62°E, 44 lks.
 L-9 South 1/4 Cor. of Sec. 24. D.N.R. on 8-1-62 6" J. Pine, S33°W, 29 lks. & 8" J. Pine, N53°E, 47½ lks.
 B-9 South 1/4 Cor. of Sec. 19 D.N.R. on 10-23-62 7" J. Pine, S45°W, 31½ lks. & 6" J. Pine, N60°E, 37 lks.
 13 S.E. 1/16 Cor. of Sec. 12 D.N.R. on 6-1-65 12" Y. Pine, N34°W, 41 lks. & 12" Y. Pine, S69°E, 19 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-3 Distances on N.B.T.'S. from corner I placed 5-7-63 were reversed.
 L-9 N.E. J. Pine had been cut. Re-witt. this corner as placed by myself 8-1-62 from corner location perpetuated by R.L.S. Schaaf.
 B-9 7" J. Pine bearing was recorded wrong. SE in stead of SW.
 13 N.W. Y. Pine had died. Re-witt. this corner as placed by R.L.S. Bray 6-1-65.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 D.N.R. Monument. Bearings: 16" R. Pine, N38°E, 29.04' & 14" R. Pine, S62°E, 42.24'.
 L-9 D.N.R. Monument. Bearings: 6" Dead J. Pine, S33°W, 19.14' & 7" R. Pine, N23°E, 79.7' & 11" R. Pine, S79°W, 128.0'.
 B-9 D.N.R. Monument. Bearings: 7" J. Pine, S45°E, 20.79' & 6" R. Pine, N60°E, 24.42'.
 13 D.N.R. Monument. Bearings: 12" Y. Pine, S69°E, 12.54' & 12" R. Pine, N17°W, 30.55'.

SIGNED BY

Billy D. Buckler
 Billy D. Buckler

DATE 9-26-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

