

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. R. 11 X. W.	K-5, L-7, G-7, I-8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-5 S.W. Sec. Corner of Sec. 12. D.N.R. on 5-7-58. 7" R. Pine, N80°E, 36 lks. & 5" R. Pine, S55°W, 21½ lks. & 8" R. Pine, N39°W, 31½ lks.
 L-7 South 1/4 Corner of Sec. 13. D.N.R. on 6-23-59. 11" J. Pine, N60°E, 28 lks. & 11" J. Pine, N85°W, 48 lks.
 G-7 S.W. Sec. Corner of Sec. 15. D.N.R. on 7-21-60. 18" R. Pine, N30°E, 56 lks. & 8" R. Pine, S70°W, 44½ lks. & 7" R. Pine, S47°E, 45 lks.
 I-8 West 1/4 Corner of Sec. 23. D.N.R. on 7-21-60. 20" R. Pine, S55°E, 60 lks. & 13" R. Pine, S29°W, 58½ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-5 S.W. R. Pine had been cut. Re-witt. corner as placed by myself on 5-7-58 at corner location perpetuated by R.L.S. Schaaf.
 L-7 N.W. J. Pine had been cut. Re-witt. corner as placed by myself on 6-23-59 from perpetuated corner location of R.L.S. Schaaf.
 G-7 N.E. R. Pine has been cut. Re-witt. corner as placed by myself on 7-21-60, at intersection of firelines.
 I-8 S.E. R. Pine has been cut. Re-witt. corner as placed by myself on 7-21-60 from O.B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5 D.N.R. Monument. Bearings: 7" R. Pine, N80°E, 23.76' & 8" R. Pine, N39°W, 20.79' & 6" R. Pine, S38°W, 30.7'.
 L-7 2" Iron Pipe. Bearings: 11" J. Pine, N60°E, 18.48' & 8" R. Pine, S30°W, 74.0' & 8" Oak, S20°E, 58.5'.
 G-7 2" Pipe, buried. Bearings: 8" R. Pine, S70°W, 29.37' & 7" R. Pine, S47°E, 29.70' & 6" R. Pine, N40°E, 33.5'.
 I-8 2" Pipe, buried. Bearings: 13" R. Pine, S29°W, 38.61' & 6" R. Pine, N57°E, 36.5'.

SIGNED BY

Billy D. Buckler
 Billy D. Buckler

DATE 9-26-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

