

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>8</u> R. <u>11</u> W.	<u>M-6, D-11, C-5, I-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 East 1/4 Corner of Section 13. D.N.R. on 5-6-58. 12" R. Pine, N30°E, 71½ lks. & 9" R. Pine, S71°E, 31½ lks.
- D-11 North 1/4 Corner of Section 32. D.N.R. on 6-10-58. 13" R. Pine, N44°W, 44 lks. & 8" W. Pine, S54°W, 24½ lks.
- C-5 S.E. Section Corner of Sec. 7. D.N.R. on 5-26-58. 16" Hemlock, S30°W, 62 lks. & 14" Hemlock, S62°E, 29 lks. & 10" R. Pine, N74°W, 72 lks.
- I-5 S.E. Section Corner of Sec. 10 D.N.R. on 5-7-58. 9" R. Pine, S37°W 24 lks. & 7" R. Pine, N33°E, 100 lks. & 6" J. Pine, N64°W, 63½ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-6 Both witt. cut. Re-witt. corner as set by myself on 5-6-58 from O.B.T.'S.
- D-11 1" pipe with brass cap has been removed. Replaced monument as set by myself 6-10-58 from O.B.T.'S.
- C-5 S.E. Hemlock cut. Re-witt. corner as set by myself 5-26-58 from one O.B.T.
- I-5 N.E. R. Pine has been cut. Re-witt. corner as set by myself 5-7-58 at corner perpetuated by R.L.S. Schaaf.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 ½" x 16" Iron Bar, buried. Bearings: 12" R. Pine, N55°E, 48.4' & 14" R. Pine, S53°W, 61.0'.
- D-11 ½" Re-Rod. Bearings: 13" R. Pine, N44°W, 29.04' & 8" W. Pine, S54°W, 16.17'.
- C-5 ½" x 16" Iron Bar. Bearings: 16" Hemlock, S30°W, 40.92' & 10" R. Pine, N74°W, 47.52 & 6" Hemlock, S38°E, 42.5'.
- I-5 D.N.R. Monument. Bearings: 9" R. Pine, S37°W, 15.84' & 7" R. Pine, N33°E, 66.0' & 10" J. Pine, S18°E, 36.5'.

SIGNED BY _____

Billy D. Buckler
Billy D. Buckler

DATE 9-26-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

