

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

4 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>X</u> , R. <u>11</u> E. <u>X</u> S. _____ W. _____	<u>I-11, B-5, E-6, M-8</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- I-11 S.W. Section Corner of Section 26. DNR on 5-3-54. 10" S. Maple, N40°E, 27 lks. & 10" S. Maple, S64°W, 30 lks.
  - B-5 South 1/4 Corner of Section 7. DNR on 5-26-58. 13" R. Pine, S73°W, 132 lks. & 24" W. Pine Stub, N76°W, 77 lks.
  - E-6 West 1/4 Corner of Section 16. DNR on 5-26-58. 14" R. Pine, S64°W, 49 lks. & 14" R. Pine, N18°E, 45 lks.
  - M-8 East 1/4 Corner of Section 24. DNR on 5-6-58. 8" J. Pine, N44°E, 62 lks. & 8" J. Pine, S24°W, 52 lks. & 9" J. Pine, N56°W, 55½ lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-11 Replaced 1" pipe and added witt. to corner I placed myself on 5-3-54, at location of corner set by R.L.S. Schaaf.
  - B-5 W. Pine Stub gone. Re-witt. corner as set by myself 5-26-58 from O.B.T.'S.
  - E-6 Both N.B.T.'S. cut. Re-witt. corner placed by myself 5-26-58 from O.B.T.'S.
  - M-8 N.B.T.'S. cut. Re-witt. this corner as placed by myself on 5-6-58.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-11 2" Iron W/concrete bottom. Bearings: 10" S. Maple, N40°E, 17.82' & 10" S. Maple, S64°W, 19.8' & 6" Hemlock, N62°W, 11.35'.
  - B-5 D.N.R. Monument. Bearings: 13" R. Pine, S73°W, 87.12" & 8" R. Pine, N31°E, 31.4'.
  - E-6 D.N.R. Monument. Bearings: 8" R. Pine, S68°E, 30.35' & 8" R. Pine, N47°E, 19.2'.
  - M-8 D.N.R. Monument. Bearings: 8" J. Pine, (Stump), S24°W, 34.32' & 9" J. Pine, (Stump), N56°W, 36.63' & 6" R. Pine, N36°E, 121.6' & 6" R. Pine, S12°W, 61.75'.

SIGNED BY Billy D. Buckler  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 9-26-84

