

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>11</u> R. <u>K.</u> S. <u>11</u> R. <u>W.</u>	<u>7-M1</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ S. _____ R. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ S. _____ R. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-15, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Meander Corner on the East Side of Section 1 on the South Shore of Lake Superior.

O.B.T.'S.: W. Pine 10, S10 1/2° E, 136 lks. & Fir 16", S36 1/2°W, 145 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner set by retracing the Boundary Survey, Old Coast Guard Site - Gov't Lots 3 and 4, by Billy D. Buckler L.S. 6-23-75.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument set at this corner.

10" W. Pine, S56°W, 61.70'
5" Spruce, S22°W, 30.10'
8" Spruce, S07°E, 32.80'
8" Spruce, S17°E, 40.05'

SIGNED BY David B. Babbitt DATE 5-18-87

David B. Babbitt
SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____