

#111

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LUCA

County	Located in:	Corner Code //
1. Public Land Survey	T 49N R 11W	D9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on July 13, 1992, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D9) Quarter corner common to Sections 28-29. Corner previously recorded by Billy D. Buckler as recovered and monumented in 1958 at a 2" iron pipe set by Marcus Schaaf, Reg. Surveyor. Buckler's witnesses are: 12" White Pine (1/48 NBT) 849W 18.5 Links, and 13" White Pine (1/48 NBT) 839W 30.5 Links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) Found Buckler's monument, a 1" pipe with a 4" brass cap, removed from the ground, and Schaaf's pipe bent over. Remonumented the corner, as described below, at the position of Schaaf's pipe and Buckler's bearing trees, which were found as recorded. The corner lies in the center of an E-W road, buried beneath the road surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Set a 1"x32" painted iron pipe capped with a yellow plastic cap stamped "Mich. DBR LS 33986". Blazed, scribed, and set measuring nails in the following new bearing trees:

14" E. Pine 816E 30.65' (1/48 NBT)

16" W. Pine 810W 34.2' (1/48 NBT)

Reblazed the top blaze and placed measuring nails in Buckler's BT's as follows: 14" W. Pine 849W 12.5'

16" E. Pine 839W 20.8'

Signed by

Stephan J. Szyszkoski

Date

Oct. 15, 1992

Surveyor's Michigan License No.

33986

