LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For	corners	in	

on this certificate.

			•
Luce	Located In:	Corner Code #	·
(County)	-		
1. Public Land Survey	T 49N R 11W T R	E5	
2. Property Controlling in Section	S T R S T R R		
3. Miscellaneous Property in Sec.	S T R R		Register of Deeds Stamp & File Number
4. Lot No. , Red	corded Plat		ABCDEFGHIJKLM
5. Private Claims			2 6 5 4 3 2 1
ı, Stephan J. Szyszkoski , ir			4 - 7 - 1 - 8 - 10 - 10 - 12 - 12 - 12 - 12 - 12 - 12
above were in conformance with of instructions of the United States I a Court of Law and /or that the court of Law and /or the cour	74, Michigan P.A. of 1970, the corner regulations and rules therefore as require Department of the Interior, Bureau of Lacorner points mentioned in lines 3, 4 and d of Land Surveyors or by a Decree ered, found as expressed below:	ed in the current manual of surve and Management or by a decree of I 5 above were in conformance wit	ey of 6 —18 —17 —16 —15 —14 —13 — 14 —13 —
NOTE: Not more than 2 corn	ners, all in the same town and range,	. may be recorded	

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 8-9-16-17. 1854 - Record of Geo. H. Cannon, Deputy Surveyor, states: Post...corner of Sections 8-9-16-17. W.Pine 16" S62W 27 links, W.Pine 11" N41 1/2E 40 links. 1958 - Corner recovered and recorded as follows by Billy D. Buckler, RLS: "Found 2" iron pipe buried in intersection of N-S-E-W firelines. This corner was re-witnessed as set by Marcus Schaaf, Reg. Surveyor. Found two Pine stump bottoms bearing N41E, 40 links and S60W 27 links". New witnesses: 10" Red Pine S20W 55.5 links, 10" Red Pine S32E 44 links. Found no other record of the Schaaf survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 2" iron pipe of record, in good condition, buried in the intersection of firelanes N-S-E-W, and at record bearing and distance from the remaining 1958 NBT Red Pine [found as a double Red Pine 14" DBH] to the SE. The Red Pine NBT SW appears to have been removed by earthmoving equipment. The original BTs were not recovered. Accepted the pipe as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2"ID iron pipe. Set measuring nail with

MDNR tag in the side of:

14" twin R.Pine S27E 29.55' mrkd "S16" 1958 NBT

8" W.Pine N53E 27.8'

mrkd "S9 NBT"

11" R.Pine N42W 26.3'

"S8 NBT"
"S17 NBT"

12" W.Pine S58W 31.75' Bearings are magnetic.

1

STEPHAN J.
SZYSZKOSKI
LAND
SURVEYOR
No.
33986

Surveyor's Michigan License No.

33986

Date

02/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities