

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 11W	E4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/09/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 8 and 9. 1854 - Record of Geo.H.Cannon, Deputy Surveyor states: SO deg. 4' E between Sections 8 & 9 ...40.11 Quarter Section corner. W.Pine 12" N45W 9 links, W.Pine 10" S37E 16 links...SO deg. 48'E Corrected from 1/4 cor...80.25 Corner of Sections 8-9-16-17. 1961 - Corner remonumented by Billy D. Buckler RLS: "This corner was replaced as set by Marcus Schaaf, Registered Land Surveyor. Found Iron Pipe in concrete in place with both W.Pine B.T.'s in evidence". Set 1" pipe with 4" brass cap. Witnesses: 12" Red Pine S03E 38 links, 9" W.Pine N35W 113 links. Corner record dated 1/30/1962. Found no other record of the Schaaf survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The 1961 monument was not recovered and is presumed to have been destroyed by prior logging operations in the area. Found the Schaaf pipe in concrete buried at the corner position, in good condition, and at record bearing and distance from the 1961 NBTs. The Red Pine SE is in good condition with overgrown blazes. The W.Pine NW is now a cut stump with measuring notch visible. Found no evidence of the original W.Pine B.T.s. Accepted the pipe as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2" iron pipe. Placed 5/8"x18" rebar inside the pipe and set a plastic cap stamped "MICH DNR LS 33986" on the rebar. Set measuring nail with MDNR tag in the side of:
 19" R.Pine S01W 25.18' mrkd "1/4S" 1961 NBT
 9" W.Pine N31W 63.7' mrkd "1/4S NBT"
 8" R.Pine S70W 29.25' do
 8" R.Pine S79E 17.08' do
 Bearings are magnetic. Top of monument is flush with the ground.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities