

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>49</u> <sup>N.</sup> <del>X.</del> , R. <u>12</u> <sup>X.</sup> <del>W.</del>	A-1, A-2, B-1
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-26, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner set by John Burt, D.S. in 1841.

- A-1 Township Corner, T49-50N R12-13W. Bearings were: N Pine 12", S47°W, 85 lks. and N. Pine 8", N35°E, 91 lks.
- A-2 Quarter Corner on North side Section 6. Bearings were: N. Pine, 6", N85°E, 44 lks and N. Pine 10", N50°W, 21 lks.
- B-1 Quarter Corner on West side Section 6. Bearings were: Cottonwood 2", S84°E, 29 lks & Aspen 10", N14°W, 35 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**


- A-1 Found corner marked with a 6" square stone monument, marked "U.S. L.H.E."
- A-2 Corner re-established on line and by single proportion measure bet. two sec. Cors. No evidence of original corner.
- B-1 Corner re-established on line and by single proportion measure.. Found squared post 7.35' North and 3.95' West of corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- A-1 New Bearings: 8" J. Pine, N23°E, 47.6' and 8" J. Pine, N75°W, 28.8'.
- A-2 Placed 1" pipe with 4" aluminium cap at corner. New Bearings: No new witnesses available. Area is clear cut Jack Pine and flattened by scarifier.
- B-1 Placed 1" pipe with 4" aluminium cap at corner. New Bearings: 10" W. Pine, S25°W, 22.4' and 14" Red Pine, N27°W, 42.7'.

SIGNED BY Billy D. Buckler  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 2-15-77



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_