

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 12 W.

----- Ince ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 14-23 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 12" Hard Maple ----- N 56° E ----- 36 links -----
"1/4 S NBT"

12" Y. Birch ----- S 13° W ----- 20 links -----
"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from random line notes by Marcus Schaff, Reg. Surveyor.

Found possible birch stump turnout S 26° W 39 links. Found old chapped face on beech tree facing corner. Checked distance west to line tree. Very good.

Found weed pest set by T. J. McLaren, McMillan, about 15 links north.

Placed location pester 8 chs. ~~south~~ North on road.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6/26/57