

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T48-49 NR 12 W. . .

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2, 3, 34, and 35.

DESCRIPTION OF CORNER MONUMENT 2" Iron Pipe -----

WITNESSES TO CORNER 8" Cedar S 32 E 74¹/₂ Links, Marked "S 2 NBT"

8" Cedar S 39 W 25 Links, Marked "S 3 NBT"

6" Cedar N 25 E 24 Links, Marked "S 35 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was re-witnessed as set by Marcus Schaaf, Reg. Surveyor. Found 2" iron pipe in place with following B.T.'s. W. Pine N 35 W, 39 Links, tree down, in excellent condition. B. Ash S 69 E, 25 Links, tree standing but dead, face rotted out.

Corner lies in Northedge of swamp.

Corner was placed and witnessed on 6 May 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-19-59
REGISTERED LAND SURVEYOR