

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 49N N.R. 12W

Luce COUNTY


DESCRIPTION OF CORNER Sec. Cor. common to Secs; 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-20-70

WITNESSES TO CORNER..... 12" Cedar (S29 1BT) N30°W 12.3'

9" Cedar (S28 1BT) N48°E 17.8'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from original cedar witness, bearing N48°E, 22 links,
Tree is still green.

Found several signatures and blazes, dating to 1918.

Corner lies $1\frac{1}{2}$ links west of ridge and in a thick cedar swamp.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler REGISTERED LAND SURVEYOR DATE 8-26-70