

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 12W

Luce COUNTY


DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 9-16

CORNER MONUMENT 1" Pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-18-70

WITNESSES TO CORNER..... 9" R. Pine (¼S NBT) S80°W 19.8'

9" R. Pine (¼S NBT) N13°E 53.9'



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one possible Bearing tree;

a W. Pine bearing, S82°E, 10 links.

Found remains of rotted log with old axe marks and overgrowth as well as a **stump** bottom.

Found remains of two wood stake points in the soil at the corner location.

Distance to Sec Cor. ½ mile west checks well.

Found **stump** hole at site of the second recorded witness, a Y. Birch.

Cor. found and placed with L. Rubick, Aide.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8-26-70
REGISTERED LAND SURVEYOR