

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 12W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 10-15

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8/18/70

WITNESSES TO CORNER..... 8" R. Pine (1/4 S NBT) S 38°W 28.6'



18" R. Pine (1/4 S NBT) N11°W 26.6'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner replaced from one original witness;  
a Y. Pine stamp, bearing S50°E, 14 links. Found bottom face with scribe marks  
and notch in good condition. Stamp has been cut about 24" high. Found very old  
blazes on a down, Jack pine, one chain west of the corner.  
Found no evidence of use. Cor. found and placed with L. Rubick, Forestry Aide  
on this date.

SURVEYOR'S SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/26/70  
REGISTERED LAND SURVEYOR