

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 12W


Luce COUNTY

DESCRIPTION OF CORNER  $\frac{1}{4}$  Cor. bet. Secs. 11/14

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-17-70

WITNESSES TO CORNER..... 9" B. Spruce ( $\frac{1}{4}$ S 11/14 NBT) S22°E 14.2'



9" B. Spruce ( $\frac{1}{4}$ S 11/14 NBT) S49°W 12.6'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner replaced from two original witnesses;  
a W. Pine stub, 7' high, bearing N30°E, 5 links, with complete faces and  
scribe marks evident and  
a W. Pine stump, bearing S28°W, 20 links, with bottom face still remaining.

Cor. found by L. Rubick, For. Aide

**SURVEYOR'S SEAL**

SIGNED *Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 8-26-70