

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

_____ Twp _____ COUNTY


T 40 N R 12 W

DESCRIPTION OF CORNER Section corner common to secs. 15-16-21-22

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/19/70

WITNESSES TO CORNER..... 15" Y. Birch (s 21 MBT) S.29 degrees W. 6.0'



9" Soft Maple (s 15 MBT) N.19 degrees E. 44.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at site of a wood post set by unknown Surveyor. Found remains of stump bottoms in proper position for the recorded witness trees, which were both Beech. Found an original line tree (sugar 8") on the section line, 8.51 chains west of this corner.

Corner found and placed with L. Rubick, Forestry Aide, Lake Superior State Forest.

SURVEYOR'S SEAL

SIGNED

Billy D. Euckler
BILLY D. EUCKLER

DATE

8/26/70

DISTRIBUTION:

REGISTERED LAND SURVEYOR

~~County Courthouse~~

Area Forester (Regions I & II)

District or Region Surveyor

Forestry Div., Lansing

R 4047

Rev. 10/68