

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>E.</u> , R. <u>12</u> W.	K-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buchler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 10-24 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner bet. Secs: 35-36, set by Francis Coleman, D.S., 1851.

Bearings were:
 Hemlock 14" N10°W 12 Links
 Hemlock 9" S25°E 12 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner replaced at a squared wood post, set by unknown Surveyor. Found remains of one probable witness, S25°E, 12 Links. Distance North to a small pond checks well.
 Corner lies 1 chain North of a Woods Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed a 1" pipe with 4" aluminium cap at corner.

New Bearings:
 20" W. Pine N9°W 14.3' and 9" Soft maple N60°E 10.5'

SIGNED BY Billy D. Buchler DATE 12/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 257 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____