

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Lucan Co. Two Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>40</u> N. <u>8</u> R. <u>12</u> E. <u>W.</u>	C-11 D-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12/1 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- C-11 Sec. Cor. 29-30-31-32, set by Francis Coleman, D.S., 1851.
Bearings were:
W. Pine 30" N43°W 18 Links and hemlock 16" S67°E 23 Links.
 - D-11 Corner bet. Secs. 29-32, set by Francis Coleman, D.S., 1851.
Bearings were:
Fir 5" N48°W 10 Lks. and hemlock S54°E 29 Links.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- C-11 Corner replaced from remains of the W. Pine witness; a 30" stump. Found remains of blazed and scribe marks. Corner lies on top of a knob, as record notes indicate.
 - D-11 Corner replaced from one possible witness; a hemlock in proper position. Found original Y. Birch line tree 641' East of corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Placed 1" pipe with 4" aluminium cap at both corners.
- C-11 New Bearings:
12" hemlock N17°E 30.8' and 10" hemlock S47°W 46.3'
 - D-11 New Bearings:
16" hemlock N63°W 32.5' and 16" Hemlock S14°E 12.8' and
10" hemlock S58°W 35.3'

SIGNED BY Billy D. Buckler DATE 12/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8857 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)