

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>8</u> R. <u>12</u> E. <u>W.</u>	G-11 <u>H-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 11/27 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-11 Sec. Cor. 27-28-33-34, set by Francis Coleman, D.S., 1851.
Bearings were:
Fir 12" $145^{\circ}W$ 25 Lks. and Fir 12" $349^{\circ}E$ 18 Lks.

H-11 $\frac{1}{2}$ Corner bet. Secs. 27-34, set by Francis Coleman, D.S., 1851.
Bearings were:
Beech 7" $123^{\circ}W$ 23 Lks. and Hemlock 14" $S22^{\circ}E$ 27 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-11 Replaced corner at an old wood post, set by unknown surveyor. Position checks well with $\frac{1}{2}$ Corner, $\frac{1}{2}$ mile West and Sec. Cor. 1 mile East.

H-11 Replaced corner at an old wood post, set by unknown surveyor. Position checks with corners, $\frac{1}{2}$ mile to East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at both corners.

G-11 New Bearings: 14" Soft Maple $N21^{\circ}W$ 17.4' and 16" Soft Maple $S25^{\circ}W$ 14.5'

H-11 New Bearings: 14" hemlock $N32^{\circ}W$ 32.2' and 14" hemlock $S12^{\circ}E$ 40.1'

SIGNED BY Billy D. Buckler DATE 12/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8807 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____