

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 12 W.	C-6 C-7
2. PROPERTY CONTROLLING IN SECTION	T. S. R.	E. W.
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R.	E. W.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 2/13 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- C-6 1/4 Cor. bet. Secs: 17-18, set by Francis Coleman, D.S. 1851.
 Bearings were:
 Cedar 4" N57°W 11 lks and Tamarack 8" S31°E 11 lks.
 - C-7 Sec. Cor. 17-18-19-20, set by Francis Coleman, D.S. 1851.
 Bearings were:
 Spruce 12" N35°E 21 lks and Cedar 14" S64°W 14 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-6 Found squared wood post in place with the Cedar witness, now 9", still green. Faces are grown over. Tamarack is a rotted stump, found remains of face with a few axe and scribe marks. Found following names and dates written on the Cedar witness; (S. Lowney Jr. - T. Pelto - Nov. 1931) and (P. W. Semer - H. M. Osborne - 7/12/40).
 - C-7 Found squared wood post in place with a down cedar in proper position. Found an original line tree (Record = 8" Cedar-1.74 chs.- west of corner.) Cedar is now 20". Notches have been exposed by R. Kadchiffe, R.L.S., 4/3/57.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at both corners.

- C-6 New Bearings:
 14" W. Pine N60°E 22.3' and 9" Cedar S4°W 21.8'
- C-7 New Bearings:
 18" Cedar S11°W 39.7' and 18" Cedar S48°E 15.3'

SIGNED BY Billy D. Buckler DATE 3/5/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____