

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>49</u> ^{N.} S. , R. <u>12</u> ^{X.} W.	B-3 A-4
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5/4 & 5/5, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners set by John Burt, D.S. in 1841.

B-3 $\frac{1}{4}$ Cor. on Northside Sec. 7.
Bearings were:

Y. Birch 10, N60°W 8 lks.
Fir 8, S37°E 16 lks.

A-4 $\frac{1}{4}$ Cor. on Westside of Sec. 7.
Bearings were:

Sugar 6, S8°E, 24 lks.
Sugar 6, N58°W, 10 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-3 Re-established corner by single proportionate measure between section corners.

A-4 Corner re-established midway and on line between two section corners. No evidence of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

B-3 New Bearings:

15" W. Spruce, S54°E, 22.9'
18" W. Spruce, N2°E, 32.2'

A-4 New Bearings:


20" Soft Maple, N62°W, 17.6'
12" Beech, S47°E, 29.1'

SIGNED BY _____

Billy D. Buckler
Billy D. Buckler

DATE 10-5-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____

DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____