

MAR 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R12W	A4 ✓
	T49N R13W	M4
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LUCE COUNTY
REGISTER OF DEEDS

Recorded
Liber 3 Page 913
02-08-2000 13:04:11
Kathy S. Mahar
Kathy S. Mahar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on March 7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A4: PLS - John Burt, DS, 1841, Set qr. section post - Sugar 6", S.08° E., 24 links, Sugar 6", N.58° W., 10 links. ***** CCI Forestry Division, Land and Timber Examination Report, T.J. McLaren, 1950, documented 6" post at corner position. No references were given. ***** Michigan Department of Natural Resources Billy D. Buckler, RLS, 1977. ** Corner reestablished midway and on line between two section corners. No evidence of original corner. Set 1" pipe w/4" aluminum cap and established the following references. ** Maple 20", N.62° W., 17.6 feet; ** Beech 12", S.47° E., 29.1 feet. ** No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A4: Found 1" G.I.P. with 4" aluminum cap on a 6" flat faced wood post 3 feet high. Also found two BT's from the report of 1977 in good condition. Corner position checks well with other corners of Section 12 documented by a section subdivision survey performed in 1985 by a local surveyor. ** Established additional BT's and upgraded existing BT's to current Alger County standards. ** Monument position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A4: Stamped P.A. 345 in existing 4" aluminum capped monument. Renewed existing reference trees w/BT signs and paint. Established additional reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measure w/aluminum I.D. washers in the following reference trees. ** Ex. Maple 24", N.61° W., 18.33 feet, "Blzd"; ** Ex. Beech 16", S.44° E., 29.46 feet "BH Blz. NBT"; ** Maple 8", N.14° E., 59.52 feet "1/4s BT"; ** Beech 12", S.37° W., 49.29 feet, "1/4s BT". ** Survey marker sign on six foot steel post, S.63° W., 1.0 feet. ** All bearings are magnetic.



Signed by Robert L. Jamros Date June 12, 1996
Surveyor's Michigan License No. 25849

