

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T49N R12W	A 5 ✓
	T49N R13W	M 5
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 3 Page 912*  
02-08-2000 13:04:03  
*Kathy S. Mahan*  
Kathy S. Mahan, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4		3		2	1
3												
4	7			8			9		10		11	12
5												
6	18			17			16		15		14	13
7												
8	19			20			21		22		23	24
9												
10	30			29			28		27		26	25
11												
12	31			32			33		34		35	36
13												

I, Robert L. Jamros, in a field survey on June 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M5: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Set post corner of Secs. 12 & 13. Birch 20, S.77°W., 4 links. Birch 12, N.77°E., 11 links. \*\*\*\*\* Billy D. Buckler, RLS, 1956. Replaced section corner as perpetuated by Marcus Schaaf, RLS No. 3104. Set 1" G.I.P. with 4" brass cap. Witnesses, 4" W. Pine, N.80°E., 23 links, 6" Soft Maple, N.01°E., 74 links. \* Liber 2, Page 141, Alger County Corner Records. \*\*\*\*\* C.C.I. Co. Land Corner Records. J.R. Radcliffe, RLS, 1966. Found monument and all BT's of the 1956 report in good condition. No new witnesses were made. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M5: Located corner position by standard field survey and single proportionate measurements to adjacent corners. Found monument and accessories of the 1956 report in good condition and in acceptable position. Established additional references. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M5: Existing 1" G.I.P. with brass cap. Established 2 new reference trees with BT signs, blazed, scribed and painted. Renewed 2 existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. \* Existing - White Pine 24", N.80°E., 14.87 feet; \* Existing - Maple 9", S.01°E., 26.14 feet; \* Maple 5", S.48° W., 59.44 feet, "BT"; \* Maple 4", N.53°W., 40.68 feet, "BT". \* Survey marker sign on 6 foot steel post, S.85°E., 1.0 feet. All bearings of new references are magnetic.

Signed by *Robert L. Jamros* Date December 16, 1998  
Surveyor's Michigan License No. 25849

