

**SURVEY &
REMONUMENTATION**

MAR 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LUCE COUNTY
REGISTER OF DEEDS

Recorded
Liber 3 Page 909
02-08-2000 13:03:35
Kathy S. Naba
Kathy S. Naba, Register
REGISTER OF DEEDS

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R12W	A 8 ✓
	T49N R13W	M 8
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Robert L. Jamros, in a field survey on July 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M8: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Set quarter section corner. Fir 8, S.41°E., 28 links. Mountain Ash 4, N.51°W., 21 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M8: Located and established corner position by standard field survey and single proportionate measurement between BT section corners ½ mile North and South. Search was made for GLO evidence, inconclusive. Evidence of blaze lines to the North, South and West. Monumented corner position and established new reference trees. Position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M8: Set Berntsen aluminum monument with 3 1/4" aluminum cap no. AINB30, stamped to identify corner position. Established the following reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following reference trees. * Maple 16", N.65°E., 25.37 feet, "1/4S BT"; * Maple 6", S.20°E., 11.96 feet, "1/4S BT"; * Maple 10", S.29°W., 15.10 feet, "1/4S BT"; * Maple 12", N.37°W., 21.05 feet, "1/4S BT". * Survey marker sign on 6 foot steel post, N.60°W., 1.0 feet. All bearings are magnetic.



Signed by Robert L. Jamros Date December 16, 1998
Surveyor's Michigan License No. 25849

