

MAR 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LUCE COUNTY  
REGISTER OF DEEDS

Recorded  
*Liber 3 Page 908*  
02-08-2000 13:03:28  
*Kathy S. Mahan*  
Kathy S. Mahan, Register  
REGISTER OF DEEDS

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R12W	A 9 ✓
	T49N R13W	M 9
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on July 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M9: P.L.S. - John Burt, DS, for William A. Burt, DS, 1841. Hemlock 22, corner of Sections 24 and 25, Spruce 13, N.52°W., 28 links. \*\*\*\*\* Billy D. Buckler, RLS, 1960. This corner was replaced from evidence of blazes on old down Hemlock which may have been the corner tree in the original notes. Measurements to corners in vicinity check well. Set 1" G.I.P. with brass cap. Witnesses, 7" Soft Maple (S30 NBT), S.02°E., 51 links, 5" Soft Maple (S24 NBT), N.74°W., 16 links. \* Liber 2, Page 107, Alger County Corner Records \*\*\*\*\* C.C.I. Co., Land Corner Reports. J.R. Radcliffe, RLS, 1966. Found monument and all BT's of the 1960 report in good condition. No new witnesses were made. \*\*\*\*\* No other record of restoration.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M9: Located corner position by standard field survey and single proportionate measurements. Found monument of the 1960 land corner report in good condition and in the center of the remains of a Hemlock stump. Evidence of GLO Spruce BT in the Northwest position no longer remains. Established additional reference trees in addition to the 2 existing BT's of the 1960 report. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M9: Existing 1" G.I.P. with brass cap. Established 2 new reference trees with BT signs, blazed, scribed and painted. Renewed 2 existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following reference trees. \* Balsam 5", S.48°E., 26.51 feet, "S30 BT"; \* Maple 8", N.34°E., 10.38 feet, "S19 BT"; \* Existing - triple Maple 2", S.02°W., 34.35 feet; \* Existing - Maple 8", N.74°W., 10.59 feet. \* Survey marker sign on 6 foot steel post, N.70° W., 1.0 feet. All bearings of new references are magnetic.

Signed by Robert L. Jamros Date December 16, 1998  
Surveyor's Michigan License No. 25849

