

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	G9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 01/13/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1851 - Established by Francis Colman Deputy Surveyor. Set post. Sugar 12" N72E 29 links, W.Birch 8" S60W 28 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner position by double proportionate measurement to the original record between monumented corners 2649.69' north (40.325 ch. GLO), 5309.70' east (80.56 ch. GLO), 5299.11' south (80.65 ch. GLO), and 5245.92' west (79.59 ch. GLO).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" Spruce S28W 5.64' mrkd "S28 NBT"  
 10" Maple N44W 7.28' "S21 NBT"  
 12" Maple N27E 30.42' "S22 NBT"  
 6" Maple N86E 28.57' "S22 NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 03/22/2010  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities