

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	G10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. 1851 - Established by Francis Colman Deputy Surveyor, midway and on the Section line between Section corners 40.325 chains north and south. Set post. Beech 9" N64W 23 links, Sugar 3" S42E 14 links. 1977 - Billy D. Buckler RLS remonumented the corner at the position of a wood post that checked with an original W.Pine line tree 561.6' South. Set 1" Pipe with 4" aluminum cap. 10" Maple N24W 30.7', 16" Maple East 8.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) The original post and accessories were not recovered. The 1977 monument and accessories were not recovered, despite several searches. Found no evidence of the position of the original corner or of the 1977 position on the ground. Reestablished the corner midway and on the Section line between monumented Section corners 2649.55' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Maple S21W 15.52' mrkd "1/4S NBT"
 12" Maple S63W 22.35' do
 12" Maple N10W 40.64' do
 8" Maple N69E 19.1' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 03/22/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities