

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	G8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11/10/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G8) Quarter corner common to Sections 21 and 22. 1851 - Established by Francis Colman Deputy Surveyor, midway and on the Section line between Section corners 40.325 chains north and south. Set post. W.Birch 8" N43W 42 links, Hemlock 14" S49E 31 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G8) Remonumented the corner in the original position at record bearing and distance from the 1851 Hemlock OBT, found a standing dead stub, 14" DBH, with upper blaze open, scribing "1/4" visible, and subsequent penciled signatures. Also found the ground-level remains of the OBT W.Birch at record bearing and distance. The original post point was not recovered. Found the distance to perpetuated original Section corner north to be 2655.21' and the distance to reestablished Section corner south to be 2649.69'. This corner was recovered and remonumented by T.H.Stark and J.A.Nutkins, Michigan Dept. of Natural Resources, Newberry Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" Hemlock S12W 9.3' mrkd "1/4S NBT"
 6" Balsam N73E 7.26' do
 10" Maple N45W 44.38' do
 6" Maple S53W 11.88' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 03/22/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities