

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 12W	E10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29	●		28		27			26	25
11													
12	31			32			33		34			35	36
13													

I, Stephan J. Szyszkoski, in a field survey on 12/01/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E10) Quarter corner common to Sections 28 and 29. 1851 - Established by Francis Colman Deputy Surveyor, midway and on the Section line between Section corners 40.195 chains north and south. Set post. Cedar 12" N51E 28 links, Cedar 18" S60W 15 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E10) Remonumented the corner in the original position and at the position of an old down cedar post, rotted off at ground, found at record bearing and distance from the remains of the two OBT Cedars. The Cedars had both been windthrown. Found remains of the upper blaze with axe mark and overgrowth on the Cedar N51E and remains of the lower blaze with axe notch and overgrowth on the Cedar S60W. No scribing observed on either tree - the portions of the blazes which might display such marks have rotted away. Drove the old cedar post adjacent to the newly-installed monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 21" Cedar N17W 28.05' mrkd "1/4S NBT"
 10" Cedar N47E 16.33' do
 22" Cedar S30E 18.56' do
 5" Cedar S56W 15.3' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 03/22/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities