

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>27</u> T <u>49N</u> R <u>12W</u>	<u>15</u>
	S <u>28</u> T _____ R <u>12W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 8 01/19/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15-Sec.27) West 1/16 corner between Sections 27 and 34. Not established in the original survey.

(8-Sec. 28) West 1/16 corner, Section 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 27) Established the corner midway and on the Section line between Section corner 1320.50' west and Quarter corner 1320.50' east.

(8-Sec. 28) Established the corner midway and on a straight line between Quarter corner 1323.01' west and the intersection of 1/4 lines of Section 28 1323.01' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Hemlock N49W 16.55' mrkd "W1/16 BT"
 16" Hemlock S63W 37.15' do
 22" Maple S16W 11.95' do
 14" Maple N86E 15.7' do
 Bearings are magnetic.

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Hemlock N46E 58.82 mrkd "W1/16 BT"
 14" Maple N29W 15.73' do
 12" Spruce N89W 8.47' do
 6" Spruce S05E 54.64' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/22/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management