LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce (County) Located In: Corner Code #

1. Public Land Survey		T		R			
		T		R			
		T		R			
2. Property Controlling	S 27	T	49N	R	12W	10	
in Section	S 28	T	49N	R	12W	5	
	S	T		R			
3. Miscellaneous	S	T		R			
Property in Sec.	S	T		R			

4. Lot No. _____, Recorded Plat _____

5. Private Claims

Register of Deeds Stamp & File Number



I, Stephan J. Szyszkoski, in a field survey on 10 12/08/2009 5 12/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 27) South 1/16 corner between Sections 27 and 28. Not established in the original survey.

(5-Sec. 28) North 1/16 corner, Section 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 27) Established the corner midway and on the Section line between Quarter corner 1324.78' north and Section corner 1324.78' south.

(5-Sec. 28) Established the corner midway and on a straight line between Quarter corner 1329.73' north and the intersection of 1/4 lines of Section 28 1329.73' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
16" Maple S84W 46.8' mrkd "S1/16 BT"
11" Maple S03W 44.5' do
18" Y.Birch S63E 19.75' do
14" Maple S88E 30.58' do
Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
20" Maple S41W 18.44' mrkd "N1/16 BT"
6" Maple N09W 29.16' do
6" Maple N18E 24.17' do
12" twin Maple S68E 19.81' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 03/22/2010

Surveyor's Michigan License No. 33986

STATE OF MICHIGAN STEPHAN J. SZYSZKOSKI LAND SURVEYOR No. 33986 LICENSED LAND SURVEYOR

For the Michigan Department of Natural Resources and Environment, Office of Land and Facilities

47323

47324

FORM APPROVED BY MICHIGAN STATE BOARD OF LICENSED SURVEYORS, 1971
Revised July 14, 1975
Revised Jan., 1983
Revised Oct., 1995