

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>27</u> T <u>49N</u> R <u>12W</u>	<u>7</u>
	S <u>27</u> T <u>49N</u> R <u>12W</u>	<u>14</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 7 10/29/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (7-Sec. 27) North 1/16 corner between Sections 26 and 27. Not established in the original survey.
- (14-Sec. 27) South 1/16 corner between Sections 26 and 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (7-Sec. 27) Established the corner midway and on the Section line between Section corner 1327.13' north and Quarter corner 1327.13' south.
- (14-Sec. 27) Established the corner midway and on the Section line between Section corner 1328.14' south and Quarter corner 1328.14' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (7) Set 5/8"x24" rebar with plastic MDNR cap flush with ground. Set measuring nail with MDNR tag in the side of:
10" W.Pine East 17.7' mrkd "N1/16 BT"
15" twin R.Pine S51E 28.2' do
11" J.Pine N88W 34.77' do
10" J.Pine N44W 28.22' do
C/L N-S firelane is 10' west.
Bearings are magnetic. | (14) Set 5/8"x24" rebar with plastic MDNR cap 6" below ground. Set measuring nail with MDNR tag in the side of:
13" R.Pine N77E 18.65' mrkd "S1/16 BT"
8" W.Pine S38E 26.95' do
12" W.Pine S43W 23.25' do
8" W.Pine N18W 48.35' do
C/L of N-S firelane is 1 ft. East.
Bearings are magnetic. |
|---|--|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/22/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management