

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	I11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I11) Corner common to Sections 26-27-34-35. 1851 - Established by Francis Colman, Deputy Surveyor. Set post corner of Sections 26,27,34,35. W.Pine 24" N67W 15 links, Hemlock 16" S34E 16 links. Marcus Schaaf RLS remonumented this corner, date unknown, with a 2" iron pipe. Found no direct record of Mr. Schaaf's survey. 1959 - Billy D. Buckler RLS recovered the 2" iron pipe placed by Mr. Schaaf, found in the intersection of firelines N-E. Placed 1" pipe with 4" brass cap at the corner. NBTs 17" W.Pine N24W 94 links, 36" W.Pine stub S80W 23 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I11) The original post and accessories were not recovered. Found the 1959 monument of record, with the 2" iron pipe by Mr. Schaaf, adjacent. Both are in good condition. The 1959 W.Pine NBT NW is in place, in good condition, at record bearing and distance. The NBT 36" W.Pine stub was not recovered. I accepted the monument as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I11) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Found 2" I.pipe adjacent. Set measuring nail with MDNR tag in the side of:  
 26" W.Pine N19W 63.35' mrkd "S27" 1959 NBT  
 6" W.Pine N80W 6.05' mrkd "S27 NBT"  
 11" R.Pine S24E 62.0' "S35 NBT"  
 16" R.Pine N65E 47.85' "S26 NBT"  
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 04/14/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division