

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	I10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 09/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I10) Quarter corner common to Sections 26 and 27. 1851 - Established by Francis Colman, Deputy Surveyor, midway and on the Section line between Section corners 40.235 chains north and south. Set post. Hemlock 24" N18W 15 links, Hemlock 15" S29E 22 links. Marcus Schaaf RLS remonumented the corner with a 2" iron pipe, date unknown. No direct record of the Schaaf survey was found. 1959 - Billy D. Buckler, RLS found the 2" pipe set by Mr. Schaaf and remonumented the Schaaf position with a 1" ID I. pipe with 4" brass cap. NBTs 14" W.Pine S78E 59 links, 12" W.Pine S58W 21 links. Corner lies in west side of N-S fireline.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I10) The original post and accessories were not recovered. Found the 1959 monument in good condition and at record bearing and distance from the 1959 NBTs, both in good condition with overgrown blazes. The monument is located 3.3' west and 1.0' north of a position which is midway and on line between Section corners north and south and I accept the position of the monument as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I10) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 20" W.Pine S72E 39.45' mrkd "1/4S" 1959 NBT  
 21" W.Pine S62W 15.1' do do do  
 8" W.Pine S31E 60.15' mrkd "1/4S NBT"  
 9" W.Pine N41W 23.55' do do do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/14/2010  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division