

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 12W	19
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 07/14/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I9) Corner common to Sections 22-23-26-27. 1851 - Established by Francis Colman, Deputy Surveyor. Set post. Maple 7" N20W 15 links, Sugar 8" S40E 65 links. Marcus Schaaf RLS remonumented the corner with a 2" ID Iron Pipe, date unknown. No direct record of the Schaaf survey was found. 1959 - Billy D. Buckler RLS recovered the 2" pipe set by Mr. Schaaf at record bearing and distance from the original BT Maple NW (fd. N36W 15 links) and replaced it with a 1" ID I.pipe with 4" brass cap. Corner lies at the intersection of firelines S. and E. NBTs 18" W.Pine S30W 61 links, 10" S.Maple N46E 55 links, 9" S.Maple S42E 37 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I9) Recovered the 1959 monument in good condition and at record bearing and distance from the three 1959 NBTs, all in good condition with overgrown blazes. The original BT Maple NW is in place, now 24" DBH, still green, and checks with the 1959 record. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I9) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 24" Maple N37W 11.6' mrkd "S22" 1851 BT  
 15" Maple N53E 36.0' "S23" 1959 NBT  
 13" Maple S36E 24.7' "S26" do  
 31" W.Pine S32W 41.7' "S27" do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/14/2010  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division