

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	G7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/16/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. 1851 - Established by Francis Colman, Deputy Surveyor. Set post. Beech 12" N42W 34 links, Beech 10" S73E 74 links. 1970 - Billy D. Buckler RLS remonumented the corner at the position of a wood post, set by an unknown surveyor, found at record bearing and distance from the stump bottoms of both Beech BTs. Found an original line tree (sugar 8") on the section line, 8.51 ch. west of the corner [at the original GLO record position]. Set 1"ID I.pipe with 4" aluminum cap. 15" Y.Birch S29W 6.0', 9" Soft Maple N19E 44.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Found the 1970 monument in good condition and at record bearing and distance from the 1970 NBTs. The Y.Birch SW is dead, the Maple NE is in good condition. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" Maple N24E 44.1' mrkd "S15" 1970 NBT
 4" Maple S38E 17.6' mrkd "S22 NBT"
 16" Hemlock N54W 58.65' "S16 NBT"
 7" Sugar N01W 25.9' "S16 NBT"
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 04/14/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division