

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>49N</u> R <u>12W</u>	<u>E9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 07/16/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. 1851 - Established by Francis Colman, Deputy Surveyor. Set post. Birch 10" N41W 18 links, Sugar 12" S72E 15 links. 1977 - Billy D. Buckler RLS remonumented the corner from the original BT sugar: "...replaced from original Sugar B.T. Bearing should be S27E rather than the recorded "S72E". Tree has been cut; is now 30" in diameter, inside 12" rotted out. Found imprint of scribe marks on the overgrowth". Set 1"ID I.pipe with 4" aluminum cap. 10" Maple N29E 44.3', 16" Maple S55W 32.7', 8" Maple S30E 34.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) Found the 1977 monument in good condition. Found the 1977 NBTs in good condition with upper and lower blazes overgrown, all exhibiting some difference with the 1977 record. Two of the NBTs are of significantly larger diameter than given in the record. The third is at a distance which differs by 5' from the record. I accept the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Maple N43W 8.5' mrkd "S20 NBT"
 20" Maple N31E 44.75' mrkd "S21" 1977 NBT
 18" Maple S27E 35.35' mrkd "S28" do
 16" Maple S48W 27.2' mrkd "S27" do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/14/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division