

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 12W	E11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S T _____ R _____	_____
	S T _____ R _____	_____
3. Miscellaneous Property in Sec.	S T _____ R _____	_____
	S T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10/15/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E11) Corner common to Sections 28-29-32-33. 1851 - Established by Francis Colman, Deputy Surveyor. Set post. Cedar 8" N48E 22 links, Cedar 9" S30W 6 links. 1970 - Billy D. Buckler RLS remonumented the corner at record bearing and distance from the original BT Cedar N48E 22 links, found in good condition. He found several signatures and blazes, dating to 1918. Corner was noted as being 1.5 links west of a ridge in a thick cedar swamp. Set 1"ID I.pipe with 4" alum. cap. 12" Cedar N30W 12.3', 9" Cedar N48E 17.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) Found the 1970 monument in good condition and at record bearing and distance from the 1970 NBTs, now both down. The original BT Cedar N48E was not recovered. Found that the ridge, noted in the 1970 record, is not 1.5 links distant, but 1.5 chains distant. I accept the monument as a careful and faithful perpetuation of the position of the original corner. The corner lies in a very thick cedar swamp. Many trees down.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E11) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Cedar S49W 17.75' mrkd "S32 NBT"
 4" Balsam N48E 20.9' mrkd "S28 NBT" nail set high
 4" Cedar S80E 3.95' "S33 NBT"
 4" Cedar S45E 10.25' "S33 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/14/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division