

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| Luce | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T 49N R 12W | H11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 11/02/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H11) Quarter corner common to Sections 27 and 34. 1851 - Established by Francis Colman, Deputy Surveyor, midway and on the Section line between Section corners 40.23 chains east and west. Set post. Beech 7" N23W 23 links, Hemlock 14" S22E 27 links. 1972 - Billy D. Buckler RLS remonumented the corner at the position of an old wood post, by an unknown surveyor, found to check in position with corners 1/2 mile east and west. Set 1"ID I.pipe with 4" aluminum cap. 14" Hemlock N32W 32.2', 14" Hemlock S12E 48.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H11) The original post and accessories were not recovered. Found the 1972 monument in good condition and at record bearing and distance from the 1972 NBTs, both in good condition. Found the monument to be 0.7' north and 1.9' west of the record position between Section corners and accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 19" Hemlock N31W 32.55' mrkd "1/4S" 1972 NBT
 18" Hemlock S10E 48.5' do do
 7" Hemlock S34W 14.95' mrkd "1/4S NBT"
 5" Maple S61E 11.9' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/14/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division