

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Luce</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 49N R 12W | G11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 10/29/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Sections 27-28-33-34. 1851 - Established by Francis Colman, Deputy Surveyor. Set post. Fir 12" N45W 25 links, Sugar 12" S49E 18 links. 1972 - Billy D. Buckler RLS remonumented the corner at the position of an old wood post, by an unknown surveyor, the position of which was found to check well with 1/4 corner 1/2 mile West and with Section corner 1 mile to East. Set 1" ID I.pipe with 4" alum. cap. 14" Soft Maple N21W 17.4', 16" Soft Maple S25W 14.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) The original post and accessories were not recovered. Found the 1972 monument in good condition and at record bearing and distance from the 1972 NBTs, both standing dead. Distances to 1/4 corner west 2632.2' (2645.3' GLO) and to Section corner east 5285.8' (5310.4' GLO), check very well, proportionately, with the original record. I accept the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Fd. 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Maple S55E 14.95' mrkd "S34 NBT"
 9" Maple N54W 23.37' "S28 NBT"
 20" Maple S29W 30.25' "S33 NBT"
 8" Cherry N87E 37.73' "S27 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/14/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division