

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 12W	F11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S T _____ R _____	_____
	S T _____ R _____	_____
3. Miscellaneous Property in Sec.	S T _____ R _____	_____
	S T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 10/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28-33. 1851 - Established by Francis Colman, Deputy Surveyor, midway and on the Section line between Section corners 40.08 chains east and west. Set post. Cedar 10" N30W 35 links, Cedar 10" S18E 32 links. 1970 - Billy D. Buckler RLS remonumented the corner at record bearing and distance from an the original Cedar BT N30W 35 links, found green. He also found several blazes by timber cruisers dating to 1931. Set 1"ID I.pipe with 4" aluminum cap. BTs: 10" Cedar N12E 13.3', 10" Cedar S61E 24.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) Found the 1970 monument in good condition and at record bearing and distance from the 1970 NBTs. The Cedar NE is down, the Cedar SE is in good condition but its bearing is noted incorrectly in the 1970 record. It was found S61W, not S61E from the corner. The original Cedar BT N30W is in place, green, with open blaze, at record bearing and distance. I accept the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Cedar S61W 24.25' open blaze 1970 NBT  
 16" Cedar N25W 22.9' do 1851 BT  
 9" Cedar S19E 12.0' mrkd "1/4S NBT"  
 10" Cedar N80E 15.9' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/14/2010  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division