

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>27</u> T <u>49N</u> R <u>12W</u>	<u>2</u>
	S <u>27</u> T <u>49N</u> R <u>12W</u>	<u>16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11								●					
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 16 01/16/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(2-Sec. 27) East 1/16 corner between Sections 22-27. Not established in the original survey.

(16-Sec. 27) East 1/16 corner between Sections 27 and 34. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(2-Sec. 27) Established the corner midway and on the section line between Quarter corner 1327.42' west and Section corner 1327.42' east.

(16-Sec. 27) Established the corner midway and on the section line between Quarter corner 1322.42' west and Section corner 1322.42' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 12" Maple N88W 5.75' mrkd "E1/16 BT"  
 12" Hemlock S45W 29.2' do  
 10" Hemlock S18W 13.5' do  
 14" Hemlock N67E 44.5' do  
 Bearings are magnetic.

(16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 10" Hemlock S05E 26.54' mrkd "E1/16 BT"  
 14" Hemlock East 3.9' do  
 14" Hemlock N41E 11.9' do  
 12" Maple N15W 8.07' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 04/15/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division