

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.50... NR. 8.W...

Luce

COUNTY

DESCRIPTION OF CORNER Meander Corner for Sections 28-33 on SE Shore of
Bodi Lake

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 16" White Pine N72°E - 191 Links
Marked "M.C. NBT"

9" Red Pine S80°E - 88 Links
Marked "M.C. NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Replaced from two White Pine B.T.s bearing S28°W 65 links and N75°E 96 links.
Found scribe marks on stump bottoms.

Note: Section Corner common to Sections 28-29-32-33 would lie 3.50 chains
West in Lake.

Corner placed and witnessed March 5, 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 12/5/58
REGISTERED LAND SURVEYOR